

## Eliminate waste and accelerate timelines with critical concrete and ambient data at your fingertips.



Reduce labour on-site with realtime data on your desktop or device.



Monitor mass concrete to stay confident you're meeting local specifications for maximum temperature and temperature differentials. This includes using PBTDL to allow for more flexibility.



Properly equip yourself to keep your concrete construction projects advancing in hot or cold weather.



Have confidence in sustainable mixes.



Our mission is to build a brighter future where concrete construction is more efficient, sustainable and safe. Call us to discover how our solutions can advance your precast business.

## **Device Specifications**

Produce to project specifications and eliminate product rejections by monitoring your critical data in real time. Material temperatures, ambient temperature and relative humidity are available at a glance with seamless reporting and alerts.

|                                 | EXACT                           | EXACT       | 20150<br>WEST SLAB   | EXACT        | EXACT       |
|---------------------------------|---------------------------------|-------------|----------------------|--------------|-------------|
|                                 | Flex Logger                     | Relay V2    | Embeddable<br>Logger | Pro Logger   | Relay       |
| Technology                      | Monitor 2.0                     | Monitor 2.0 | Monitor 1.0          | Monitor 1.0  | Monitor 1.0 |
| Communication                   | LTE-M, LoRa                     | LTE-M, LoRa | LoRa                 | LoRa         | LTE-M, LoRa |
| GPS                             | Yes                             | Yes         | No                   | No           | No          |
| BLE Offline Reclaim             | Yes                             | Yes         | No                   | No           | No          |
| Probe Ports                     | 4                               | 0           | 4                    | 4            | 0           |
| Ambient                         | Yes                             | Yes         | Yes                  | Yes          | Yes         |
| Optional<br>Humidity            | Yes                             | No          | No                   | Yes          | No          |
| Charging Port                   | Yes                             | Yes         | No                   | No           | Yes         |
| Remote Firmware<br>Updates      | Yes                             | Yes         | No                   | No           | Yes         |
| Remote Fault Detection          | Yes                             | Yes         | No                   | No           | No          |
| Battery Life @ 15 min Reporting | 4 months (LTE) 24 months (LoRa) | 4 months    | 1 month              | 18 months    | 1 month     |
| Memory                          | 90 days                         | N/A         | 21 days              | 21 days      | N/A         |
| Connector Type                  | 4-pin                           | N/A         | 2-pin barrel         | 2-pin barrel | N/A         |
| Digital Probe Support           | Yes                             | No          | No                   | No           | No          |



Our mission is to build a brighter future where concrete construction is more efficient, sustainable and safe. Call us to discover how our solutions can advance your precast business.